

PTI Information for MSD Treatment Facilities							
Facility Name	Avg. Daily Flow (MG) Based on Dec. 2017	Design Capacity (MGD)	Design Year*	Proposed Flows (ADF plus connections under construction or being designed)	Federal Permit #	Ohio Permit #	Planned Upgrades
Fort Scott	0.014	0.25	2009	Contact Steve Parker 244- 1351	OH0134198	1PC00016*CD	Influent currently hauled off to another facility.
Indian Creek	0.67	1.5	1998		OH0024678	1PK00020*ID	
Little Miami	26.67	55	1996		OH0025453	1PL00000*QD	
Mayflower Estates	0.04	0.08	1971		OH0025623	1PG00018*GD	
Mill Creek	90.55	130	1989		OH0025461	1PM00001*MD	
Muddy Creek	13.38	15	1971		OH0025470	1PK00006*LD	
Polk Run	4.97	8	2005		OH0020419	1PK00019*HD	
Sycamore	6.97	9	2010		OH0025488	1PK00005*LD	
Taylor Creek	2.92	5.5	1993		OH0040983	1PK00015*ED	

* Design Year refers to the year of substantial completion of the most recent treatment facility upgrade to increase the dry weather Average Daily Flow (ADF) capacity.

** Proposed flow should be obtained immediately before submitting a PTI. This information can be left blank on draft versions of a PTI.

Last Updated April 23, 2018